# WORLD INTELLECTUAL PROPERTY ORGANIZATION International Bureau



## INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 7:

B32B 5/04, 5/26, B29C 55/02, 55/08, B32B 3/30, B29C 55/00, 55/18, A61F 13/15, A41D 13/00 (11) International Publication Number:

WO 00/38913

(43) International Publication Date:

6 July 2000 (06.07.00)

(21) International Application Number:

PCT/US99/30729

A1

US

(22) International Filing Date:

21 December 1999 (21.12.99)

(30) Priority Data:

60/113,737 23 December 1998 (23.12.98) 09/455,513 6 December 1999 (06.12.99)

(71) Applicant: KIMBERLY-CLARK WORLDWIDE, INC. [US/US]; 401 N. Lake Street, Neenah, WI 54956 (US).

(72) Inventors: MORMAN, Michael, Tod; 555 Kings Peak, Alpharetta, GA 30022 (US). SCHWARTZ, Robert, John; 3575 Sweetwater Drive, Cumming, GA 30041 (US). WELCH, Howard, Martin; 328 West Lane, Woodstock, GA 30188 (US). HWANG, Patricia, Hsiaoyin; 10300 Rillridge Court, Alpharetta, GA 30022 (US).

(74) Agents: MOYLES, Lisa, J. et al.; Kimberly-Clark Worldwide, Inc., 401 N. Lake St., Neenah, WI 54956 (US).


(81) Designated States: AE, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, DE, DK, DM, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, UZ, VN, YU, ZA, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

#### Published

With international search report.

Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.

(54) Title: TRANSVERSELY EXTENSIBLE AND RETRACTABLE NECKED LAMINATE OF NON-ELASTIC SHEET LAYERS



#### (57) Abstract

The present invention is directed to a necked laminate and a process for making the laminate. The necked laminate is formed from sheet layers of at least one non-elastic neckable material laminated to at least one non-elastic film defining a longitudinal and transverse dimension wherein the laminate is extensible and retractable in at least one dimension without significantly reducing the breathability and/or liquid barrier properties of the film layer. This laminate extensibility and retractability is the result of striated rugosities in, for instance, the longitudinal dimension of the film layer which enables the necked laminate to have an amount of extensibility and retractability in the transverse dimension. The laminate is made by first partially stretching the non-elastic film layer, attaching a non-elastic neckable layer to form a laminate and then stretching the laminate to neck the laminate and stretch the film to its desired fully stretched configuration.

# FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain .	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
ΑU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ,	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgimm	GN	Guinea	MK	The former Yugoslav	TM	Turkmenistan
BF	Burkina Faso	GR	Greece		Republic of Macedonia	TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
ВЈ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA	Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	zw	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's	NZ	New Zealand		
CM	Cameroon		Republic of Korea	PL	Poland		
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakstan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
DE	Germany	LI	Liechtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singapore		

# TRANSVERSELY EXTENSIBLE AND RETRACTABLE NECKED LAMINATE OF NON-ELASTIC SHEET LAYERS

# Field of the Invention

The present invention is directed to a necked laminate and a process for making the laminate. The necked laminate is formed from sheet layers of at least one non-elastic neckable material laminated to at least one non-elastic film defining a longitudinal and transverse dimension wherein the laminate is extensible and retractable in at least one dimension without significantly reducing the breathability and/or liquid barrier properties of the film layer. This laminate extensibility and retractability is the result of striated rugosities in, for instance, the longitudinal dimension of the film layer which enables the necked laminate to have an amount of extensibility and retractability in the transverse dimension.

5

10

15

20

25

## Background of the Invention

Laminates of film and nonwoven web layers are known to be useful in personal care absorbent articles such as diapers, training pants, incontinence garments, mattress pads, wipers, feminine care products (e.g. sanitary napkins), in medical applications such as surgical drapes and gowns, facemasks, and wound dressings and wraps, in articles of clothing or portions thereof including industrial workwear and lab coats, and the like.

These laminates are made such that the article can be produced with relatively low cost and are thus disposable after only one or a few uses. Much research and development continues, however, to achieve "cloth-like" visual and tactile qualities in these articles without sacrificing breathability and low cost, while also providing an article that is liquid-impermeable. In particular, one disadvantage of such articles is that the laminate used to make the article does not "give" like, for instance, a fabric made from cotton, which due to its fiber and yarn structure, has a natural ability to extend and retract. These properties are necessary to allow the article to conform to the user's body, thereby feeling and appearing to be more "cloth-like". One known solution to this problem has

been to incorporate elastomeric or elastic materials into the article. Unfortunately, incorporation of such materials generally results in increased costs due to the more expensive materials. If breathability is attained by stretching a filled film to form micropores, there are problems associated with maintaining breathability of filled elastic films since the recovery of the elastic material after stretching generally closes or partially closes the micropores which had been created for breathability.

5

10

15

20

25

Heretofore, to provide laminates with transverse extensibility and retractability, nonwoven web layers were necked (as defined below) prior to applying an elastomeric sheet made using an elastomeric polymer as described in, for instance, commonly assigned U.S. Patent No. 5,336,545 to Morman. Necking of the nonwoven web allowed it to extend in the transverse direction. Without the elastic sheet attached to the nonwoven web, however, the laminate would not have significant recovery force after the extension.

Prior art laminates made from non-elastic materials which were used as, for example, waistband components in articles such as diapers, have been made to be more conformable by first stretching an elastic waistband, then attaching the laminate to the stretched waistband such that when the waistband retracts, it draws in the laminate. A problem with this design is that the laminate is difficult to gather or bunch and the resulting product has minimal extensibility and retractability. Such bunched laminates are also very difficult to fabricate, have a cheap appearance and are uncomfortable when in contact with the body.

The present invention avoids these and other difficulties by providing an inexpensive, necked laminate which achieves transverse extensibility and retractability using non-elastic materials without compromising other properties such as breathability, liquid barrier properties and strength.

**Summary of the Invention** 

The present invention is directed to a necked laminate and a process for making the laminate. The necked laminate is formed from sheet layers of at least one non-elastic

neckable material laminated to at least one non-elastic film defining a longitudinal and transverse dimension wherein the laminate is extensible and retractable in at least one dimension without significantly reducing the breathability and/or liquid barrier properties of the film layer. This laminate extensibility and retractability is the result of striated rugosities in, for instance, the longitudinal dimension of the film layer which enables the necked laminate to have an amount of extensibility and retractability in the transverse dimension. A breathable laminate may be made by first partially stretching the non-elastic film layer, attaching a non-elastic neckable layer to form a laminate and then stretching the laminate to neck the laminate and lengthen the film to its desired fully stretched configuration.

### **Brief Description of the Drawings**

Figure 1 is a schematic representation of an exemplary process for forming the transversely extensible and retractable necked laminate of the present invention.

10

15

20

25

Figures 2 is a top plan view of the laminate of the present invention as it is being necked showing the striated rugosities in the longitudinal dimension.

Figure 3 is a perspective view of the process of Figure 1 showing the stretching of the non-elastic film layer, attachment of the non-elastic neckable material and the necking of the laminate.

Figure 4 is a partially cut-away top plan view of an exemplary personal care absorbent article, in this case a diaper, which may utilize the necked laminate according to the present invention.

Figure 5 is a plan view of an exemplary medical article, in this case a facemask, which may utilize the necked laminate according to the present invention.

Figure 6 is a top plan view of an optical photo micrograph (High Resolution Digital Image) of the non-elastic film layer side of a laminate of the present invention showing the striated rugosities.

Figure 6a is a top plan view of an optical photo micrograph of the enlarged section of Figure 6 showing the variation and randomness of the striated rugosities.

Figures 7, 8, and 9 are cross-sectional optical photo micrographs of the laminates of the present invention showing trapezoidal, pleated, and crenellated striations, respectively.

Figure 10 is an oblique view of an optical photo micrograph of a prior art laminate.

Figures 11a, 11b, 11c, 12a, 12b and 12c graphically illustrate load versus extension curves for various samples.

5

15

20

25

Figures 14-15 graphically illustrate enlarged curves of load versus extension for various samples.

#### **Detailed Description of the Invention**

The present invention is directed to a necked laminate and a process for making the laminate. The necked laminate is formed from sheet layers of at least one non-elastic neckable material laminated to at least one non-elastic film defining a longitudinal and transverse dimension, wherein the laminate is extensible and retractable in at least one dimension without significantly reducing the breathability and/or liquid barrier properties of the film layer. This laminate extensibility and retractability is the result of striated rugosities in, for instance, the longitudinal dimension of the film layer which enable the necked laminate to have an amount of extensibility and retractability in the transverse dimension. The necked laminate is made, for example, by first partially stretching the non-elastic film layer, attaching a non-elastic neckable layer to the film layer to form a laminate, and then stretching the laminate to neck the laminate and to complete the stretching/orientation of the film layer to its desired fully stretched configuration. When a laminate is "fully stretched" it exhibits properties completely sufficient for the intended use, for example, breathability and tensile strength. As used herein, the term "partially stretched" means that the film and/or laminate is not fully stretched.

As used herein, the term "neck" or "neck stretch" interchangeably means that the laminate is drawn such that it is extended under conditions reducing its width or its transverse dimension by drawing and elongating to increase the length of the fabric. The controlled drawing may take place under cool temperatures, room temperature or greater temperatures and is limited to an increase in overall dimension in the direction being drawn up to the elongation required to break the laminate, which in most cases is about 1.2 to 1.6 times. When relaxed, the laminate does not retract toward its original longitudinal dimension or extend to its original transverse dimension, but instead essentially maintains its necked dimension. The necking process typically involves unwinding a sheet from a supply roll and passing it through a brake nip roll assembly driven at a given linear speed. A take-up roll or nip, operating at a linear speed higher than the brake nip roll, draws the fabric and generates the tension needed to elongate and neck the fabric. U.S. Patent No. 4,965,122 issued to Morman, and commonly assigned to the assignee of the present invention, discloses a reversibly necked nonwoven material which may be formed by necking the material, then heating the necked material, followed by cooling and is incorporated herein by reference in its entirety. The heating of the necked material causes additional crystallization of the polymer giving it a partial heat set.

10

15

20

25

As used herein, the term "neckable material or layer" means any material which can be necked such as a nonwoven, woven, or knitted material. As used herein, the term "necked material" refers to any material which has been drawn in at least one dimension, (e.g. lengthwise), reducing the transverse dimension, (e.g. width), such that when the drawing force is removed, the material can be pulled back to its original width. The necked material has a higher basis weight per unit area than the un-necked material. When the necked material is pulled back to its original un-necked width, it should have about the same basis weight as the un-necked material. This differs from stretching/orienting the film layer, during which the film is thinned and the basis weight is reduced.

The term "laminate" as used herein means a combination made up of at least two sheet layers wherein at least one sheet layer is a film layer and at least one sheet layer is

a layer of neckable material. Also, the term "longitudinal direction" or "LD" means the length of a material in the direction in which the material is moving when it is produced. The "longitudinal dimension" therefore, is the dimension of the longitudinal direction. The term "transverse direction" or "TD" means the width of the material, i.e. a direction generally perpendicular to the longitudinal direction. Likewise, the "transverse dimension" therefore, is the dimension of the transverse direction.

10

15

20

25

Referring to Figure 1, there is schematically illustrated an exemplary process 10 for forming the transversely extensible and retractable necked laminate 2 of the present invention. For all of the figures, like reference numerals represent the same or equivalent structure or element. A non-elastic film layer 12 is unwound from a first supply roll 16 and fed into a stretching means 20 using guide rollers 26. Once in the stretching means 20, the non-elastic film layer 12 is partially stretched in a longitudinal direction by stretching rollers 24 which stretch and thin the film layer 12. Such stretching usually occurs with little or no necking of the film layer. If the distance between the rolls is too large, irreversible narrowing of the film layer can occur. After partially stretching the film layer 12 and prior to laminating to the neckable material 14, the tension of the film layer 12 is only that which is sufficient to keep the layer from sagging. In other words, it is not necessary to continue stretching film layer 12 between the stretching means 20 and laminating means 30. A non-elastic neckable material 14, likewise is unwound from second supply rol! 18 which rotates in the direction of the arrows associated therewith. In an embodiment where partial film stretching is controlled to avoid film necking, matching the film width to the width of the neckable material is facilitated. It should be understood that the non-elastic neckable material and/or film layer may just as well be formed in-line rather than being pre-made and unwound. Adhesive sprayer 34 applies adhesive to the surface of the neckable material 14 which is then laminated to the film layer 12 using laminating means 30 (e.g. nip rolls). The laminate could also be formed by thermal point bonding, sonic welding, point bonding, or the like. The thus formed laminate 2 is then necked by a necking means 22 (e.g. take-up roll) which may be accomplished as shown in Figure 1

wherein the surface speed  $V_0$  of laminating means 30 is less than the surface speed  $V_1$  of necking means 22. As used herein, to say that the laminate has been drawn 1X means that surface speed  $V_0$  is equal to surface speed  $V_1$ . The "necking draw", therefore, is the surface speed  $V_1$  divided by surface speed  $V_0$ . Further, the distance x between laminating means 30 and necking means 22, must be sufficient to allow for necking of the laminate, such that the transverse dimension of the laminate is less than that of the unnecked laminate. As a general rule, the distance x should be at least two times the transverse dimension (width) of the laminate. Such necking provides striated rugosities in the film and/or laminate resulting in transverse extensibility and retractability to the necked laminate 2 and more "cloth-like" aesthetics (e.g. the necked laminate is softer than prior art laminates and looks more like a woven material because of the striated rugosities). Figure 3 is essentially the same as Figure 1 except that it is a perspective view showing the necking of the laminate.

It is known that stretching and orienting a filled film layer causes micropores to form in the film, but longitudinal striated rugosities do not typically form in the film layer when stretched. The film layer would instead become physically thinner and may narrow slightly. Further, to then attempt to elongate the oriented filled film layer in the TD could result in tearing when very little force is applied, which is likely due to tearing along the LD microslits which have formed from stretching and orienting the filled film layer. The polymer used to make the film, the amount of filler, and how much the film was totally drawn affects how much the film can be TD extended before it splits. By necking the laminate, the non-elastic neckable material, which is attached to the non-elastic film layer, will neck and bring the non-elastic film layer with it, thereby forming the longitudinal striated rugosities in the film which allow the film layer to extend and retract in the TD without adversely affecting the breathability and/or barrier properties of the film. In Figure 2, the striated rugosities 28 are shown figuratively in the longitudinal direction LD of laminate 2 which has been necked in the transverse direction TD. The un-necked transverse dimension 32 is the dimension the laminate would have but for the necking.

The double edged arrows indicate the extensibility and retractability of the laminate in the TD. As used herein, the term "striated rugosities", refers to thin, narrow grooved, or channeled wrinkles in the non-elastic film layer 12 of necked laminate . Referring to Figure 6, the striated rugosities can be shown generally at 28 in the surface of film layer 12' of sample 6 (in the Examples below). Figure 6a is an enlarged view of Figure 6. As can be seen in these figures, the striated rugosities have a variable and random pattern. Figures 7-9 are enlarged cross-sectional end views of the laminate 2 of Figure 6 at different points along the section showing the variable striations in film layer 12' which is attached to neckable material 14'. Figure 7 generally shows a trapezoidal striation 40; Figure 8 generally shows pleats 42; while Figure 9 generally shows crenellated striations 44. As used herein, the term "crenellated" is used as in crenellated molding which, according to Webster's Third New International Dictionary, unabridged, copyright 1986, is "a molding of ... [an] indented pattern common in medieval buildings". The striated rugosities actually occur predominantly in the non-elastic film layer, but can be seen through the necked material and give the entire laminate a more cloth-like appearance. If one were to delaminate the film layer from the neckable material after necking, the film layer would visually retain the striated rugosities while the neckable material would not. The separated film would extend and retract in the TD much like an accordion. A theory that may be ascribed to this phenomena is that the film actually crystallizes and/or plastically deforms to some degree when forming the striated rugosities, thereby setting a "memory" into the film which works to retract the laminate once it has been extended.

10

15

20

25

By the term "non-elastic", what is meant is that the sheet layers are made from polymers that are generally considered to be inelastic. In other words, use of such inelastic polymers to form the sheet layers would result in sheet layers which are not elastic. As used herein, the term "elastic" means any material which, upon application of a biasing force, is stretchable, that is, elongatable, at least about 60 percent (i.e., to a stretched, biased length which is at least about 160 percent of its relaxed unbiased length), and which will immediately recover at least 55 percent of its elongation upon

release of the stretching, elongating force. By "immediately" what is meant is that the elastic material will behave, for instance, as a rubber band to recover as soon as the elongating force is removed. A hypothetical example would be a one (1) inch sample of a material which is elongatable to at least 1.60 inches (4.06 cm) and which, upon being elongated to 1.60 inches (4.06 cm) and released, will immediately, i.e. within less than one second, recover to a length of not more than 1.27 inches (3.23 cm). Many elastic materials may be elongated by much more than 60 percent, for example, 100 percent or more, and many of these will recover to substantially their initial relaxed length, for example, to within 105 percent of their initial relaxed length upon release of the stretching force.

5

10

15

20

25

The terms "extensible and retractable" have been chosen to describe what the laminate made of non-elastic sheet layers of the present invention does upon application and removal of a biasing force. Those having skill in the art of elastic materials have conventionally used the phraseology "stretch and recover" to describe what an elastic material does upon application and removal of a biasing force as described above.

For purposes of the present invention, wherein the materials used to form the sheet layers are not elastic, the terminology chosen to describe the phenomena exhibited by the laminate upon application and removal of a biasing force is "extensible and retractable". The laminates of the present invention do not stretch as far as that of a highly elastic material, which can stretch in excess of 500%. In fact, the film portion of the laminate does not actually stretch; instead, the striated rugosities are essentially temporarily removed when a biasing force is applied in the transverse direction. If these striated rugosities are not permanently removed by, for instance, overextending the laminate in the transverse dimension or heating the extended laminate to impart a "new" memory, the laminate will eventually retract to close to its original dimension. Such a property has heretofore been unknown in laminates made solely from non-elastic neckable and film materials.

As used herein, the term "polymer" generally includes, but is not limited to, homopolymers, copolymers, for example, block, graft, random and alternating copolymers, terpolymers, etc. and blends and modifications thereof. Such blends include blends of inelastic polymers with elastic polymers as long as the elastic polymers are used in such a quantity and composition that the use of these would not render the polymeric film elastic. Unless otherwise specifically limited, the term "polymer" shall include all possible geometrical configurations of the molecule. These configurations include, but are not limited to, isotactic, syndiotactic and random symmetries.

The non-elastic film layer 12 can be made from either cast or blown film equipment, can be coextruded and can be embossed if so desired. The film layer may be made from any suitable non-elastic polymer composition.

10

15

20

Such polymers include but are not limited to non-elastic extrudable polymers such as polyolefin or a blend of polyolefins, nylon, polyester and ethylene vinyl alcohol. More particularly, useful polyolefins include polypropylene and polyethylene. Other useful polymers include those described in U.S. Patent No. 4,777,073 to Sheth, assigned to Exxon Chemical Patents Inc., such as a copolymer of polypropylene and low density polyethylene or linear low density polyethylene.

Other useful polymers include those referred to as single site catalyzed polymers such as "metallocene" polymers produced according to a metallocene process and which have limited elastic properties. The term "metallocene-catalyzed polymers" as used herein includes those polymer materials that are produced by the polymerization of at least ethylene using metallocenes or constrained geometry catalysts, a class of organometallic complexes, as catalysts. For example, a common metallocene is ferrocene, a complex of a metal between two cyclopentadienyl (Cp) ligands. Metallocene process catalysts include bis(n-butylcyclopentadienyl)titanium dichloride, bis(n-butylcyclopentadienyl)zirconium dichloride, bis(cyclopentadienyl)scandium chloride, bis(indenyl)zirconium dichloride, bis(methylcyclopentadienyl)titanium dichloride, bis(methylcyclopentadienyl)titanium dichloride, bis(methylcyclopentadienyl)titanium dichloride,

trichloride, ferrocene, hafnocene dichloride, isopropyl(cyclopentadienyl,-1-flourenyl)zirconium dichloride, molybdocene dichloride, nickelocene, niobocene dichloride, ruthenocene, titanocene dichloride, zirconocene chloride hydride, zirconocene dichloride, among others. A more exhaustive list of such compounds is included in U.S. Patent 5,374,696 to Rosen et al. and assigned to the Dow Chemical Company. Such compounds are also discussed in U.S. Patent 5,064,802 to Stevens et al. and also assigned to Dow.

Such metallocene polymers are available from Exxon Chemical Company of Baytown, Texas under the trade name EXXPOL® for polypropylene based polymers and EXACT® for polyethylene based polymers. Dow Chemical Company of Midland, Michigan has polymers commercially available under the name ENGAGE®. Preferably, the metallocene polymers are selected from copolymers of ethylene and 1-butene, copolymers of ethylene and 1-octene and combinations thereof. For a more detailed description of the metallocene polymers and the process for producing same which are useful in the present invention, see commonly assigned U.S. Patent application Serial Nos. 774,852 and 854,658 first filed on 27-December-1996 in the names of Gwaltney et al., which is incorporated herein by reference in its entirety. In general, the metallocene-derived ethylene-based polymers of the present invention have a density of at least 0.900 g/cc.

10

15

20

25

The non-elastic film layer may be a multi-layered film layer which may include a core layer, or "B" layer, and one or more skin layers, or "A" layers, on either side or both sides of the core layer. When more than one skin layer is present, is not a requirement that the skin layers be the same. For instance, there may be an A layer and an A' layer. Any of the polymers discussed above are suitable for use as a core layer of a multi-layered film. Any of the fillers disclosed herein are suitable for use in any film layer.

The skin layer will typically include extrudable thermoplastic polymers and/or additives which provide specialized properties to the non-elastic film layer. Thus, the skin layer may be made from polymers which provide such properties as antimicrobial, barrier, water vapor transmission, adhesion and/or antiblocking properties. The polymers are thus

chosen for the particular attributes desired. Examples of possible polymers that may be used alone or in combination include homopolymers, copolymers and blends of polyolefins as well as ethylene vinyl acetate (EVA), ethylene ethyl acrylate (EEA), ethylene acrylic acid (EAA), ethylene methyl acrylate (EMA), ethylene butyl acrylate (EBA), polyester (PET), nylon (PA), ethylene vinyl alcohol (EVOH), polystyrene (PS), polyurethane (PU), and olefinic thermoplastic elastomers which are multistep reactor products wherein an amorphous ethylene propylene random copolymer is molecularly dispersed in a predominately semicrystalline high polypropylene monomer/low ethylene monomer continuous matrix. The skin layer can be formed of any semicrystalline or amorphous polymer, including one that is elastic. However, the skin layer is generally a polyolefin such as polyethylene, polypropylene, polybutylene or a ethylene-propylene copolymer, but may also be wholly or partly polyamide such as nylon, polyester such as polyethylene terephthalate, polyvinylidene fluoride, polyacrylate such as poly(methyl methacrylate)(only in blends) and the like, and blends thereof.

10

15

20

25

The non-elastic film layers of the present invention can be made from breathable or non-breathable materials. The non-elastic film layer may contain such fillers as micropore developing fillers, e.g. calcium carbonate; opacifying agents, e.g. titanium dioxide; and antiblock additives, e.g. diatomaceous earth.

Fillers may be incorporated for developing micropores during orientation of the non-elastic film layer resulting in breathable films. Once the particle-filled film has been formed, it is then either stretched or crushed to create pathways through the film layer. Generally, to qualify as being "breathable" for the present invention, the resultant laminate should have a water vapor transmission rate (WVTR) of at least about 250 g/m²/24 hours as may be measured by a test method as described below. Preferably, the laminate will have a WVTR of at least about 1000 g/m²/24 hours.

As used herein, a "micropore developing filler" is meant to include particulates and other forms of materials which can be added to the polymer and which will not chemically interfere with or adversely affect the extruded film but are able to be uniformly

dispersed throughout the film layer. Generally, the micropore developing fillers will be in particulate form and usually will have somewhat of a spherical shape with average particle sizes in the range of about 0.5 to about 8 microns. The non-elastic film layer will usually contain at least about 20 volume percent, preferably about 20 to about 45 volume percent, of micropore developing filler based upon the total volume of the film layer. Both organic and inorganic micropore developing fillers are contemplated to be within the scope of the present invention provided that they do not interfere with the film formation process, the breathability of the resultant non-elastic film layer, the liquid barrier properties of the film layer or its ability to bond to another sheet layer.

10

15

20

25

Examples of micropore developing fillers include calcium carbonate (CaCO<sub>3</sub>), various kinds of clay, silica (SiO<sub>2</sub>), alumina, barium sulfate, sodium carbonate, talc, magnesium sulfate, titanium dioxide, zeolites, aluminum sulfate, cellulose-type powders, diatomaceous earth, magnesium sulfate, magnesium carbonate, barium carbonate, kaolin, mica, carbon, calcium oxide, magnesium oxide, aluminum hydroxide, pulp powder, wood powder, cellulose derivative, polymer particles, chitin and chitin derivatives. The micropore developing filler particles may optionally be coated with a fatty acid, such as stearic acid, or a larger chain fatty acid than starch such as behenic acid, which may facilitate the free flow of the particles (in bulk) and their ease of dispersion into the polymer matrix. Silica-containing fillers may also be present in an effective amount to provide antiblocking properties.

The non-elastic neckable material of the present invention is air-permeable. Such non-elastic neckable materials include nonwoven webs, woven materials and knitted materials. As used herein, the term "nonwoven fabric or web" means a web having a structure of individual fibers or threads which are interlaid, but not in an identifiable manner as in a knitted fabric. Nonwoven fabrics or webs have been formed from many processes, for example, bonded carded web processes, meltblowing processes and spunbonding processes. The basis weight of nonwoven fabrics is usually expressed in ounces of material per square yard (osy) or grams per square meter (gsm) and the fiber

diameters useful are usually expressed in microns. (Note that to convert from osy to gsm, multiply osy by 33.91). The non-elastic neckable material of the present invention has a basis weight of 5 to 90 gsm, preferably 10 to 90 gsm, more preferably 20 to 60 gsm.

The non-elastic neckable material is preferably formed from at least one member selected from fibers and filaments of inelastic polymers. Such polymers include polyesters, for example, polyethylene terephthalate, polyolefins, for example, polyethylene and polypropylene, polyamides, for example, nylon 6 and nylon 66. These fibers or filaments are used alone or in a mixture of two or more thereof.

Suitable fibers for forming the neckable material 14 include natural and synthetic fibers as well as bicomponent, multi-component, and shaped polymer fibers. A plurality of neckable materials may also be used according to the present invention. Examples of such materials can include, for example, spunbond/meltblown composites and spunbond/meltblown/spunbond composites such as are taught in Brock et al., U.S. Patent No. 4,041,203 which is incorporated herein by reference in its entirety. Neckable materials may also be formed from "coform" as described in commonly assigned U.S. Patent No. 4,100,324 to Anderson et al.

10

15

20

25

As used herein, the term "spunbonded fibers" refers to small diameter fibers which are formed by extruding through one or more extruders attached to one or more banks made up of at least transfer piping and spinplates to produce molten thermoplastic material as filaments from a plurality of fine, usually circular, capillaries in a spinneret with the diameter of the extruded filaments then being rapidly reduced as by, for example, in Appel et al., U.S. Patent No. 4,340,563; Matsuki, et al., U.S. Patent No. 3,802,817; Dorschner et al., U.S. Patent No. 3,692,618; Kinney, U.S. Patent Nos. 3,338,992 and 3,341,394; Hartman, U.S. Patent No. 3,502,763; and Dobo et al., U.S. Patent No. 3,542,615. Spunbond fibers are generally not tacky when they are deposited onto a collecting surface. Spunbond fibers are generally continuous and have average diameters (from a sample of at least 10) larger than 7 microns, more frequently, between about 10 and 40 microns. The resulting matt of fibers is then bonded to form a strong neckable

fabric. This bonding may be performed by ultrasonic bonding, chemical bonding, adhesive bonding, thermal bonding, needle punching, hydroentangling and the like.

As used herein the term "meltblown fibers" means fibers formed by extruding a molten thermoplastic material through a plurality of fine, usually circular, die capillaries as molten threads or filaments into converging high velocity, usually hot, gas (e.g. air) streams which attenuate the filaments of molten thermoplastic material to reduce their diameter, which may be to microfiber diameter. Thereafter, the meltblown fibers are carried by the high velocity gas stream and are deposited on a collecting surface to form a web of randomly dispersed meltblown fibers. Such a process is disclosed, for example, in U.S. Patent 3,849,241 to Butin et al. Meltblown fibers are microfibers which may be continuous or discontinuous, and are generally smaller than 20 microns in average diameter.

10

15

20

25

As used herein the term "microfibers" means small diameter fibers having an average diameter not greater than about 75 microns, for example, having an average diameter of from about 0.5 microns to about 50 microns, more particularly, about 2 microns to about 40 microns. Another frequently used expression of fiber diameter is denier, which is defined as grams per 9000 meters of a fiber and may be calculated as fiber diameter (in microns) squared, multiplied by the polymer density in grams/cc, multiplied by 0.00707. For the same polymer, a lower denier indicates a finer fiber and a higher denier indicates a thicker or heavier fiber. For example, the diameter of a polypropylene fiber given as 15 microns may be converted to denier by squaring, multiplying the result by 0.89 g/cc and multiplying by 0.00707. Thus, a 15 micron polypropylene fiber has a denier of about 1.42 (15<sup>2</sup> x 0.89 x 0.00707 = 1.415). Outside the United States the unit of measurement is more commonly the "tex", which is defined as the grams per kilometer of fiber. Tex may be calculated as denier/9.

Many polyolefins are available for fiber production according to the present invention, for example, fiber forming polypropylenes include Exxon Chemical Company's Escorene® PD 3445 polypropylene and Himont Chemical Company's PF-304.

Polyethylenes such as Dow Chemical's ASPUN® 6811A linear low density polyethylene, 2553 LLDPE and 25355 and 12350 high density polyethylene are also suitable polymers. The polyethylenes have melt flow rates of about 26, 40, 25 and 12, respectively. Many other polyolefins are commercially available.

5

10

15

20

The nonwoven web layer may be bonded to impart a discrete bond pattern with a prescribed bond surface area. This is known as thermal point bonding. "Thermal point bonding" involves passing a web of fibers to be bonded between a heated calender or patterned roll and an anvil roll. The calender roll is patterned so that the entire neckable material is not bonded across its entire surface. In fact, this feature is very important for necking of neckable materials as described herein. If too much bond area is present on the neckable material, it will break before it necks. If there is not enough bond area, then the neckable material will pull apart. Typically, the percent bonding area useful in the present invention ranges from around 5% to around 40% of the area of the neckable material. Many patterns for calender rolls have been developed. As will be understood by those skilled in the art, bond area percentages are, of necessity, described in approximations or ranges since bond pins are normally tapered and wear down over time. As those skilled in the art will also recognize, references to "pins/in.2" and "bonds/in.2" are somewhat interchangeable since the pins will create bonds in the substrate in essentially the same sizes and surface relationship as the pins on the roll. There are a number of discrete bond patterns which may be used. See, for example, Brock et al., U.S. Patent No. 4,041,203. One example of a pattern has points and is the Hansen Pennings or "H&P" pattern with about 200 bonds/square inch as taught in U.S. Patent 3,855,046 to Hansen and Pennings. The H&P pattern has square point or pin bonding areas wherein each pin may have a side dimension of 0.038 inches (0.965 mm), for example, resulting in a pattern having a bonded area of about 30%. Another typical point bonding pattern is the expanded Hansen and Pennings or "EHP" bond pattern which produces a bond area of about 15% to 18% which may have a square pin having a side dimension of 0.037 inches (0.94 mm), for example, and a pin density of about 100 pins/in<sup>2</sup>. Another typical

point bonding pattern designated "714" has square pin bonding areas wherein each pin may have a side dimension of 0.023 inches, for example, for a bond area of 15% to 20% and about 270 pins/in<sup>2</sup>. Other common patterns include a "Ramisch" diamond pattern with repeating diamonds having a bond area of 8% to 14% and 52 pins/in.<sup>2</sup>, a HDD pattern, which comprises point bonds having about 460 pins/in.<sup>2</sup> for a bond area of about 15% to about 23%, as well as a wire weave pattern looking as the name suggests, e.g. like a window screen and having a bond area of 15% to 20% and 302 bonds/in.<sup>2</sup>. Another bond pattern for a spunbond facing web is a "S" weave pattern as described in commonly assigned U.S. Patent No. 5,964,742 to McCormack et al. which is incorporated herein by reference in its entirety.

10

15

20

25

Laminating the film layer to the neckable material to form the laminate of the present invention may occur by typical methods known in the art including adhesive bonding, point bonding, thermal point bonding, and sonic welding. The use of inelastic and/or elastic adhesives for the adhesive bonding is contemplated herein. As discussed in more detail below, the use of an elastic adhesive has not been found to impact ease of extensibility. When the film layer and neckable material are bonded through the use of heat and/or pressure, laminating means 30 (Figure 1) such as laminating rollers may be used. The laminating rollers may be heated and point bonding may be used. The temperature at which the laminating rollers are heated depends on the properties of the film and or neckable material but is usually in the range of 200 - 275°F (93 - 135°C). The laminating rollers may each be smooth or patterned or one roll may be smooth while the other roll is patterned. If one of the rolls is patterned it will create a discrete bond pattern with a prescribed bond surface area for the resultant necked laminate 2.

Also contemplated by the present invention is the attachment of a second neckable material, which may be simply unwound and laminated to the partially stretched film, the necked laminate, or the partially necked laminate as described above or formed directly inline of the process. Such three layer laminates are particularly useful in medical and

5

10

15

20

25

industrial protective garment applications. Similarly, other film layers or partially stretched film layers may be combined.

As has been stated previously, the necked laminate 2 may be used in a wide variety of applications, including personal care absorbent articles or garments such as diapers, training pants, incontinence devices and feminine hygiene products such as sanitary napkins. The laminates resulting from the present invention are preferably more conformable to the body of the wearer resulting in better fit and comfort. An exemplary article 80, a diaper, is shown in Figure 4. Referring to Figure 4, most such personal care absorbent articles 80 include a liquid permeable top sheet or liner 82, a back sheet or outercover 84 and an absorbent core 86 disposed between and contained by the top sheet 82 and back sheet 84. Articles 80, such as diapers, may also include some type of fastening means 88 such as adhesive fastening tapes or mechanical hook and loop type fasteners to maintain the garment in place on the wearer.

The necked laminate 2 may be used to form various portions of the article including, but not limited to the back sheet 84. When using the necked laminate as back sheet 84, it is usually advantageous to place the nonwoven side facing out away from the wearer. In addition, in such embodiments it may be possible to utilize the nonwoven portion of the necked laminate as the loop portion of the hook and loop combination of fastening means 88.

As the necked laminate has TD extensibility and retractability, the elastic waistband 90 can be attached/incorporated in a non-stretched configuration during diaper production, significantly simplifying the converting process. The resulting waistband will also stretch, recover, and seal around the baby's waist much better. Necked laminates of the present invention are equally useful in articles used in medical applications. Referring to Figure 5, the necked laminate 2 has been utilized to form an exemplary article useful in medical applications, in this case a facemask 60.

Yet another exemplary article is a garment such as a lab coat or workwear. One particularly bothersome aspect of use of the prior art non-elastic laminate is the lack of

"give" as discussed above. This can be best understood in the context of bending a laminate-clad elbow. If the prior art laminate was used to create the garment, when the elbow bends, the material tightens around the elbow which may cause the material to tear or at the very least cause discomfort to the wearer. If the garment were to be made of a necked laminate of the present invention, however, the material will "give" when the elbow bends and afterwards tend to return to its prior form. The laminate would not recover with a strong force but very gently so comfort could be maintained.

5

10

15

20

25

One advantage of using necked laminate 2 in such applications is that the articles will be more "cloth-like" in both appearance and feel. Additionally, the transverse extensibility and retractability will allow the article to more closely conform to the body of the wearer.

The necked laminate of the present invention is able to maintain properties such as strength, hydrohead and breathability while getting improvements in "cloth-like" characteristics such as conformability and transverse extensibility and retractability. The advantages and other characteristics of the present invention are best illustrated by the following examples.

# **Examples**

Samples of the present invention were prepared as described below. The samples were then subjected to the following tests:

Tensile Test: The tensile test measured strength and elongation or strain of a fabric when subjected to unidirectional stress according to ASTM Standard Test D 5034-95, as well as Federal Test Methods Standard No. 191A Method 5102-78. This test measured the strength in pounds and percent stretch while elongating the sample until it broke. Higher numbers indicate a stronger and/or more stretchable fabric, respectively. The term "peak load" means the maximum load or force, expressed in pounds, required to elongate a sample to break or rupture in a tensile test. The term "strain" or "percent stretch" means the increase in length of a sample during a tensile test expressed as a percentage. Values for peak load and strain at peak load were obtained using a width of

fabric of 3 x 6 in. (76 x 152 mm), a 3 in. (76 mm) clamp width, a gauge length of 3 in. (76 mm), and a constant rate of extension of 12 inches/min. (305 mm/min.), where the entire sample width was gripped in the clamps. The specimen was clamped, for example, in an 1130 Instron, available from the Instron Corporation, or a Thwing-Albert Model INTELLECT II available from the Thwing-Albert Instrument Co., 10960 Dutton Rd., Philadelphia, Pennsylvania 19154, and the unit was zeroed, balanced and calibrated according to the standard procedure.

Breathability Test: The water vapor transmission rate (WVTR) for the sample materials was calculated generally in accordance with the following test method in order to measure the breathability of the samples. The test procedure establishes a means to determine the normalized rate of water vapor transmission through solid and porous films, nonwoven materials, and other materials while under steady state conditions. The material to be evaluated is sealed to the top of a cup of water and placed in a temperature-controlled environment. Evaporation of water in the cup results in a relatively higher vapor pressure inside the cup than the vapor pressure of the environment outside of the cup. This difference in vapor pressure causes the vapor inside the cup to flow through the test material to the outside of the cup. The rate of this flow is dependent upon the permeability of the test material sealed to the top of the cup. The difference between the beginning and ending cup weights is used to calculate the water vapor transmission rate.

10

15

20

In particular, circular samples measuring three inches in diameter were cut from each of the test materials and a control which was a piece of CELGARD® 2500 film from Hoechst Celanese Corporation. CELGARD® 2500 film is a microporous polypropylene film. The test dish was a 68-1 Vapometer cup distributed by Thwing-Albert Instrument Company of Philadelphia, Pennsylvania. One hundred milliliters of water were poured into each Vapometer cup and individual samples of the test materials and control material were placed across the open tops of the individual cups. A rubber gasket and metal ring (fitted to the cup) were placed over the sample and clamped using metal clamps. The

sample test material and control material were exposed to room temperature over a 6.5 centimeter diameter circle, having an exposed area of approximately 33.17 square centimeters. The cups were placed in an oven at about 38 °C (100°F), long enough for the cups to reach thermal equilibrium. The cups were removed from the oven, weighed, and replaced in the oven. The oven was a constant temperature oven with external air circulating through it to prevent water vapor accumulation inside. A suitable forced air oven is, for example, a Blue M Power-O-Matic 60 oven distributed by Blue M. Electric Company of Blue Ispeak, Illinois. After 24 hours, the cups were removed from the oven and weighed again. The preliminary test water vapor transmission rate values were calculated with Equation (I) below:

(I) APP MVT = (grams weight loss over 24 hours) x 7571/24 expressed in  $g/m^2/24$  hours

10

15

20

25

Approximate moisture vapor transfer is designated by "APP MVT". Under the predetermined set conditions of about 38 °C (100 °F) and ambient relative humidity, the WVTR for the CELGARD® 2500 control has been defined to be 5000 grams per square meter for 24 hours. Accordingly, the control sample was run with each test and the preliminary test values were corrected to set conditions using Equation (II) below:

(II) WVTR = (Test WVTR/control WVTR) x (5000 g/m<sup>2</sup>/24 hours)

Hydrohead: A measure of the liquid barrier properties of a fabric is the hydrohead test. The hydrohead test determines the height of water (in centimeters) which the fabric will support before a predetermined amount of liquid passes through, usually 3 drops. A fabric with a higher hydrohead reading has a greater barrier to liquid penetration than a fabric with a lower hydrohead. The hydrohead test is performed according to Federal Test Standard 191A, Method 5514 using a Textest FX-3000 Hydrostatic Head Tester available from Marlo Industries, Inc., P.O. Box 1071, Concord, North Carolina. A circular head having an inner circumference of 26 cm was used to clamp down the sample.

% Theoretical Extensibility: The % Theoretical Extensibility is the amount of extensibility and retractability that can be expected for necked laminates of the present

invention, based upon how much the original width is reduced and assuming the original laminate has no inherent extensibility. In the following equations, original width is the unnecked width (transverse dimension) of the laminate, while necked width is the width of the laminate after necking. % Theoretical Extensibility can be determined as follows:

% Theoretical Extensibility = 100 X [(original width - necked width) ÷ necked width] which can be rewritten as:

% Theoretical Extensibility = 100 X [(original width - necked width) - 1]

The % of the original width that the laminate is necked can be represented by the following equation:

% original width = 100 X (necked width  $\div$  original width) which can be rewritten as:

5

10

15

20

25

(original width  $\div$  necked width) = 100  $\div$  % original width Substituting this equation into % Theoretical Extensibility above:

% Theoretical Extensibility =  $100 \times [(100 \div \% \text{ original width}) - 1]$ So, for each sample below, the original width was measured, as was the necked width, and % Theoretical Extensibility was calculated as shown below in Table 3.

Permanent Set: The permanent set test measures the degree of retractability of a material after being stretched to a specific length. Generally, the greater the permanent set value, the less retractable the sample is. After the laminate was produced and wound onto a roll, indelible ink was used to mark a 2 in. (5.08 cm) wide strip of material in the transverse dimension. After the laminate was unwound, a sample area 3 in. (7.62 cm) (LD) x 4.5 in. (11.43 cm) (TD) was cut out of the laminate to include the marked-off area. Each sample was placed between two 3 in. (7.62 cm) wide jaws. The jaws were separated a distance of 2 in. (5.08 cm) apart and the jaws were clamped on the marks that were previously made on the material. The samples were then elongated a specified amount, 90% or 1.8 in. (4.57 cm), and allowed to retract. The elongation was recorded when the force during retraction reached 25 grams. The permanent set was calculated as follows:

Permanent set = distance between the jaws when the resistance of the laminate equaled 25 grams  $_{force}$  - initial length = x (in.) - 2 (in.) = x (cm) - 5.08 (cm).

Three repetitions were performed and the average value is represented in the examples below.

5

10

15

20

25

Example 1

A necked laminate was prepared from a non-elastic film layer and a non-elastic nonwoven web layer. A 1.5 mil layer of blown film made of 48% by weight (25 volume percent) SUPERCOAT calcium carbonate as manufactured by English China Clay America, Inc. of Sylacauga, Alabama, 47% by weight (68 volume percent) linear low density polyethylene (LLDPE) available under the trade designation DOWLEX NG3347A as manufactured by the Dow Chemical Company ("Dow"), 5% by weight (7 volume percent) low density polyethylene (LDPE) available under the trade designation 640I as manufactured by Dow, and 2000 ppm antioxidant stabilizer available under the trade designation B900 as manufactured by Ciba Specialties Company of Tarrytown, New York. The film layer, made of the composition as described above, was pre-made and wound onto a roll. To make this film layer highly breathable, it should be stretched over about 4X (4 times its original length). The film layer was then unwound from a film unwind unit into a conventional machine direction orienter, such as that manufactured by the Marshall and Williams Company, where it was partially stretched as shown in Table 1 below (stretching draw) in the machine direction to form a partially stretched, breathable film layer. Likewise, a 0.4 osy basis weight standard polypropylene spunbond having a wireweave bond pattern, such as that available from the Kimberly-Clark Corporation of Dallas, Texas, was unwound and an adhesive of 3 gsm weight (at the application point) available as H2525A from Ato-Findley of Wauwatosa, WI was applied to one surface of the nonwoven web layer using an air assisted spraying device such as a meltblown device as described in Butin et al., supra. Such devices are generally described in, for example, commonly assigned U.S. Patent No. 4,949,668 to Heindel et al.; U.S. Patent No. 4,983,109 to Miller

et al., assigned to Nordson Corporation; and U.S. Patent No. 5,728,219 to Allen et al., assigned to J&M Laboratories, Inc.

The adhesive side of the nonwoven web layer was then laminated to the partially stretched film layer using laminating rollers at a pressure of 30 pli (5.4 kg/linear cm) of a smooth resilient (rubber coated) anvil roll on one side and a smooth, unheated steel roll.

5

10

15

20

The laminate was then stretched in the longitudinal dimension and necked in the transverse dimension by passing it through a stretch nip at a greater speed than the speed of the laminating rollers (see Table 1 below - the Laminate Necking Draw column). The necking draw caused contraction (necking) of the laminate in the transverse direction.

The laminating rollers were spaced about 8 feet (2.4 m) from the stretch nip. "Total draw" in Table 1 is the necking draw multiplied by the stretching draw and was sufficient to insure enough orientation or stretching of the film layer to make it highly breathable. The thus formed transversely extensible and retractable necked laminate was then wound onto a roll. Samples were cut from the necked laminate and subjected to tests, the results of which are reported below in Table 1. Samples C1 and C2 are comparative (baseline) examples wherein the film layer was stretched as indicated, but the laminate was not necked. Figure 10 shows an oblique image of a prior art laminate of Sample C1, wherein the film layer 12 was fully stretched prior to lamination to the neckable material 14 to form the laminate, which was not subsequently necked. Sample 8 was a repeat of Sample 7. "Peak strain" is the strain at "peak load".

Table 1

5

10

Sample	Total Draw	Film Stretching Draw	Laminate Necking Draw	WVTR g/m <sup>2</sup> / 24 hr	Hydrohead mbar	LD Peak Strain %	LD Peak Load lb. (kg)	TD Peak Strain %	TD Peak Load lb. (kg)
C1	5.0X	5.0X	1.0X	2799	353	35.7	25.62 (11.62)	92.2	5.11 (2.32)
C2	3.6X	3.6X	1.0X	1759	265	66.4	23.36 (10.59)	100.8	6.16 (2.79)
3	3.9X	3.6X	1.1X	1004	316	65.6	26.33 (11.94)	100.0	6.15 (2.79)
4	4.3X	3.6X	1.2X	886	437	69.1	30.75 (13.95)	95.0	6.01 (2.73)
5	4.6X	3.6X	1.3X	1474	383	65.2	33.32 (15.11)	126.9	5.43 (2.46)
6	5.0X	3.6X	1.4X	1213	454	55.6	44.07 (19.99)	197.8	4.99 (2.26)
7	5.2X	3.6X	1.45X	-	383	48.8	35.01 (15.88)	144.3	5.46 (2.48)
8	5.2X	3.6X	1.45X	1140	387	56.0	40.20 (18.23)	141.2	4.70 (2.13)

Sample 6 had the highest TD peak strain. In this laminate, the film layer has been drawn a total of 5.0X, which is typical drawing for such articles. The laminate has additionally been necked by a 1.4X draw. The film layer of Sample C1 has also been drawn a total of 5.0X, but the laminate has not been necked at all. Even though the film layers have been drawn by the same amount, the example of the present invention, Sample 6, has a much greater TD peak strain than the comparative example, which is an indication of the improvement of the transverse extensibility and retractability of the present invention. Figures 11 and 12 graphically illustrate load versus extension curves for samples C1 and 6, while Figures 14-15 graphically illustrate enlarged curves of load versus extension curves for these samples.

Table 3 below represents necked width in inches (cm) as a function of percent stretch and shows how readily the necked laminates elongated in the transverse direction for each of the samples of Table 1. From the tensile strength test above, the force in pounds (kilograms) was recorded below in Table 2 for each sample at 30%, 60%, 90%, 120%, 150%, and 180% to break. The laminates which had been necked to a narrower width (Samples 5, 6, 8; Table #3 "Laminated Necked Width" column) elongated at a much less force at the same % elongation than the control and to a much greater extent before breaking. If the sample broke either on or before the percent step change, it has been designated as "- -".

#### 10 **Table 2**

Sample	30%	60%	90%	120%	150%	180%
C1	2.51 (1.14)	4.21 (1.91)	5.05 (2.29)	••		
C2	3.16 (1.43)	5.05 (2.29)	6.02 (2.73)			
3	2.74 (1.24)	4.88 (2.21)	5.88 (2.67)			
4	2.78 (1.26)	4.89 (2.22)	5.92 (2.69)			
5	1.30 (0.59)	2.84 (1.29)	4.41 (2.00)	5.27 (2.39)		
6	0.60 (0.27)	1.28 (0.58)	2.13 (0.97)	3.22 (1.46)	4.09 (1.86)	4.73 (2.15)
7	1.51 (0.68)	2.78 (1.26)	4.18 (1.90)	5.06 (2.30)	5.38 (2.44)	
8	1.21 (0.55)	2.33 (1.06)	3.42 (1.55)	3.89 (1.76)	4.47 (2.03)	

Table 3 additionally shows the calculated % Theoretical Extensibility as described above for each of the samples of Table 1.

Table 3

Sample	Laminate Necked Width	% Original Width	% Theoretical Extensibility	
C1	in. (cm) 12 3/8 (31.43)	100	0	
C2	12 1/4 (31.12)	99	1	
3	11 ½ (29.21)	93	7.5	
4	10 3/4 (27.31)	87	15	
5	8 3/4 (22.23)	71	41	
6	7 ½ (19.05)	61	65	
8	6 3/8 (16.19)	51	94	

The breathability was measured by WVTR for the necked laminate when it was in the TD extended configuration, since this is the configuration it would have when in use as for instance in a diaper. Three repetitions of Sample 6 were extended 100% and 166% and tested for WVTR. The results were as follows in Table 4.

5

10

15

20

Table 4

Sample 6	WVTR g/m <sup>2</sup> /24 hr
Unstretched (from Table 1 above)	1213
100% extended	3960
166% extended	4250

To better describe the TD extensibility of the film layer, for Samples C1 and 6 above, the film layer was delaminated from the spunbond layer for a further test. Prior to delamination, a length of 3 inches (7.62 cm) was marked on the film side of the laminate across the TD. The delamination was conducted by completely immersing and soaking the laminate in denatured ethyl alcohol (ethanol) which softened and partially dissolved the adhesive bonding between the film layer and spunbond layer, such that the striated rugosities of the film layer were not removed, damaged, or otherwise distorted. Once delaminated, the film layer was tested in a tensile tester as described above and the force was measured when the film layer had been extended by 0.3 inches (0.762 cm) (10% strain). The force required to extend Sample C1 (the average of three repetitions) was approximately 1000 grams per mil of the film layer thickness. The force required to extend Sample 6 (the average of three repetitions), on the other hand, was approximately 60 grams per mil of the film layer thickness, which was the thickness determined with the striated rugosities flattened out.

#### Example 2

Additional laminates were prepared as described above, except that a non-elastic adhesive was used in some samples and that some samples were heated while being

necked. The modifications were made to evaluate the impact of: 1) using a non-elastic adhesive as compared with the semi-elastic adhesive used above, and 2) heating the laminate during the necking process. For each sample, the non-elastic film layer was stretched to 4X its length prior to lamination to the spunbond layer. The laminates were necked as indicated in Table 5 and tested for permanent set as described above. The non-elastic adhesive used was Rextac 2730, available from Huntsman Polymers in Odessa, TX. Further, the samples that were heated after necking were contacted with heated rolls maintained at a temperature of about 170°F (76°C).

A 10 cm x 10 cm (3.94 in. x 3.94 in.) sample was measured while the laminate was still wound on a roll. Since the materials were wound under tension and some degree of relaxation tends to occur over time, the samples were re-measured after being cut from the roll. Samples C9 and C10 are comparative (baseline) materials wherein the film was stretched but the laminate was not necked.

10

Table 5

10

Sample	Laminate Necking Draw	Actual Draw	Adhesive Type	Heat Applied	Sample Size Measured cm (in.)	Sample Size After Relaxation cm (in.)	Permanent Set cm (in.)
C9	1.1X	1.03X	Non-elastic	No	10 x 10 (3.94 x 3.94)	10 x 10 (3.94 x 3.94)	•
C10	1.1X	1.03X	Semi-elastic	No	10 x 10 (3.94 x 3.94)	10 x 10 (3.94 x 3.94)	-
11	1.43X	1.32X	Non-elastic	No	10 x 10 (3.94 x 3.94)	10 x 12.2 (3.94 x 4.80)	3.45 (1.36)
12	1.4X	1.28X	Semi-elastic	No	10 x 10 (3.94 x 3.94)	9.6 x 11.6 (3.78 x 4.57)	3.63 (1.43)
13	1.45X	1.3X	Semi-elastic	No	10 x 10 (3.94 x 3.94)	9.5 x 11.8 (3.74 x 4.65)	3.63 (1.43)
14	1.5X	1.36X	Semi-elastic	Yes	10 x 10 (3.94 x 3.94)	10 x 10.5 (3.94 x 4.13)	3.56 (1.40)
15	1.45X	1.3X	Non-elastic	Yes	10 x 10 (3.94 x 3.94)	10 x 10.3 (3.94 x 4.06)	3.66 (1.44)
16	1.45X	1.3X	Non-elastic	No	10 x 10 (3.94 x 3.94)	10 x 11.25 (3.94 x 4.43)	3.66 (1.44)

The heat set materials, Samples 14 and 15, maintained their original dimensions better than the materials that were necked and not heat set, based on a comparison between the sample size before and after cutting from the roll. Further, all of the materials, regardless of use of elastic or inelastic adhesive, exhibited a high degree of permanent set, indicating that the materials retract upon release of a biasing force applied in the transverse dimension. There was little difference between the permanent set of the laminates made with the semi-elastic adhesive and those made with the inelastic adhesive, indicating that the small amount of elastic adhesive used does not bear on the overall extensibility and retractability of the nonwoven web laminate.

The samples were additionally tested for tensile properties in the transverse dimension (TD) and WVTR according to the test methods described above. The results are summarized in Table 6.

Table 6

5

10

Table 6							
Sample	Actual Draw	Adhesive Type	Heat Applied	TD Load at 50% Elongation lb. (kg)	TD Peak Strain %	TD Peak Load lb. (kg)	Unstretched WVTR g/m <sup>2</sup> /24 hr
С9	1.03X	Non- elastic	No	5.73 (2.60)	62.5	6.24 (2.83)	1667
C10	1.03X	Elastic	No	4.85 (2.20)	89.7	6.15 (2.79)	2121
11	1.32X	Non- elastic	No	0.0904 (0.041)	175	4.56 (2.07)	1272
12	1.28X	Elastic	No	0.375 (0.170)	201	4.72 (2.14)	1222
13	1.3X	Elastic	No	0.617 (0.280)	212	4.78 (2.17)	903
14	1.36X	Elastic	Yes	0.419 (0.190)	192	3.57 (1.62)	1482
15	1.3X	Non- elastic	Yes	0.375 (0.170)	174	3.37 (1.53)	1400
16	1.3X	Non- elastic	No	0.190 (0.086)	174	4.52 (2.05)	N/A

When the samples were elongated 50%, the control (un-necked) materials, Samples C9 and C10, exhibited a significantly higher load than the necked materials, Sample 11-16, indicating that a much greater force was needed to extend the control samples in the transverse dimension.

Having thus described the invention in detail, it should be apparent that various modifications can be made in the present invention without departing from the spirit and scope of the following claims.

#### We claim:

- 1. A necked laminate comprising:
  - a) at least one layer of a non-elastic neckable material;
  - b) at least one layer of a non-elastic film; and
  - c) a means of attaching said non-elastic neckable material to said non-elastic film to form a laminate.

wherein said laminate is necked in a first dimension and wherein said film layer has striated rugosities in a dimension perpendicular to said first dimension.

- The necked laminate of claim 1, wherein a biasing force applied to said first
  dimension of said laminate will cause said laminate to extend, and release of the
  biasing force will cause said laminate to retract.
- The necked laminate of claim 1, wherein said striated rugosities comprise trapezoidal, crenellated, or pleated striations.
- 4. The necked laminate of claim 1, wherein said means of attaching comprises point bonding, thermal point bonding, adhesive bonding, or sonic welding.
- The necked laminate of claim 4, wherein said means of attaching is adhesive bonding.
- The necked laminate of claim 1, wherein said first dimension is defined by a transverse dimension and said perpendicular dimension is defined by a longitudinal dimension.

7. The necked laminate of claim 1, wherein said laminate is breathable.

- 8. The necked laminate of claim 1, wherein said non-elastic neckable material has a basis weight of from about 0.3 osy (10 gsm) to about 2.7 osy (90 gsm).
- 9. The necked laminate of claim 1, wherein said neckable material or said non-elastic film comprises a polyolefin.
- The necked laminate of claim 1 or 9, wherein said neckable material comprises a spunbond nonwoven material.
- 11. A conformable laminate for use in a garment comprising:
  - a) at least one layer of a non-elastic neckable material;
  - b) at least one layer of a non-elastic film; and
  - c) a means of attaching said non-elastic neckable material to said non-elastic film to form a laminate,

wherein said laminate is necked in a first dimension and wherein said film layer has striated rugosities in a dimension perpendicular to said first dimension, such that a biasing force applied to said first dimension of said laminate will cause said laminate to extend and conform around the body of the wearer.

- The conformable laminate of claim 11, wherein said striated rugosities comprise trapezoidal, crenellated, or pleated striations.
- 13. The conformable laminate of claim 11, wherein said means of attaching comprises thermal point bonding, point bonding, adhesive bonding, or sonic welding.

14. The conformable laminate of claim 13, wherein said means of attaching is adhesive bonding.

- 15. The conformable laminate of claim 11, wherein said first dimension is defined by a transverse dimension and said perpendicular dimension is defined by a longitudinal dimension.
- 16. The conformable laminate of claim 11, wherein said non-elastic neckable material has a basis weight of from about 0.3 osy (10 gsm) to about 2.7 osy (90 gsm).
- 17. The conformable laminate of claim 11, wherein said laminate is breathable.
- 18. The conformable laminate of claim 11, wherein said laminate forms at least a portion of a personal care absorbent article.
- 19. The conformable laminate of claim 11, 17 or 18, wherein said laminate forms at least a portion of an outer cover for a personal care absorbent article.
- 20. The conformable laminate of claim 11, wherein said laminate forms at least a portion of a protective garment.
- 21. The conformable laminate of claim 11 or 20, wherein said laminate forms at least a portion of a facemask.
- 22. The necked laminate of claim 11, wherein said neckable material or said nonelastic film comprises a polyolefin.

23. The necked laminate of claim 11 or 22, wherein said neckable material comprises a spunbond nonwoven material.

- 24. A method for making a necked laminate comprising:
  - a) providing a non-elastic neckable material;
  - b) providing a non-elastic film layer;
  - c) attaching said non-elastic neckable material to said non-elastic film to form a laminate; and
  - d) stretching said laminate in a first dimension to neck said laminate in a dimension perpendicular to said first dimension,

such that said striated rugosities are formed in said non-elastic film layer in said perpendicular dimension.

- 25. The method of claim 24, further comprising partially stretching said non-elastic film layer prior to formation of the laminate to render said film layer in the laminate breathable.
- 26. The method of claim 25, wherein said non-elastic film layer contains from about 20% to about 45% by volume of filler.
- 27. The method of claim 25, wherein said laminate has a WVTR of at least about 1000 g/m²/24 hours.
- 28. The method of claim 24, further comprising heating said laminate.
- 29. The method of claim 24, wherein said step of attaching comprises adhesive bonding, thermal point bonding, point bonding, or sonic welding.

WO 00/38913 PCT/US99/30729

30. The method of claim 29, wherein said step of attaching is adhesive bonding.

- 31. The necked laminate of claim 24, wherein said laminate is stretched to about 1.2 to about 1.6 times its original length.
- 32. A breathable, conformable laminate for use in a garment, comprising:
  - a) at least one layer of a non-elastic neckable spunbond material having a basis weight of from about 0.3 osy (10 gsm) to about 0.7 osy (24 gsm);
  - at least one layer of a non-elastic film containing from about 20% to about
     45% by volume of filler; and
  - a means of attaching said non-elastic neckable spunbond material to said non-elastic film to form a laminate with a WVTR of at least about 1000 g/m²/24 hr,

wherein said laminate is necked in a first dimension to about 30% to about 80% of its original width, and wherein said film layer has striated rugosities in a dimension perpendicular to said first dimension, such that a biasing force applied to said first dimension of said laminate will cause said laminate to extend and conform around the body of the wearer.

- 33. A conformable laminate for use in a garment, comprising:
  - a) at least one layer of a non-elastic neckable spunbond material having a basis weight of from about 0.3 osy (10 gsm) to about 0.7 osy (24 gsm);
  - b) at least one layer of a non-elastic film;
  - a means of attaching said non-elastic neckable spunbond material to said non-elastic film to form a laminate.

wherein said laminate is necked in a first dimension to about 30% to about 80% of its original width, and wherein said film layer has striated rugosities in a dimension perpendicular to said first dimension, such that a biasing force applied to said first

WO 00/38913 PCT/US99/30729

dimension of said laminate will cause said laminate to extend and conform around the body of the wearer.

34. An extensible and retractable sheet layer comprising a non-elastic film layer, wherein said non-elastic film has striated rugosities in a first dimension such that said film will extend in a dimension perpendicular to said first dimension when a biasing force is applied in said perpendicular dimension and will retract upon release of the biasing force.





FIG. 1






FIG. 3

WO 00/38913 PCT/US99/30729




FIG. 5




FIG. 4




FIG. 6




FIG. 6a




FIG. 7




FIG. 8




FIG. 9







FIG. 10







1G. 11C






FIG. 12A









FIG. 14



Inte. onal Application No PCT/US 99/30729

			PCT/US 99	9/30729
IPC 7	B32B5/04 B32B5/26 B29C55 B29C55/00 B29C55/18 A61F13	5/02 B29C55 8/15 A41D13		33/30
According	to International Patent Classification (IPC) or to both national class	ification and IPC		
	SSEARCHED			
IPC 7	bocumentation searched (classification system followed by classifi B32B D04H B29C B29B A61F A4	cation symbols) 110		
Document	ation searched other than minimum documentation to the extent th	at such documents are inc	luded in the fields s	earched
Bectronic	cata base consulted during the international search (name of data	base and, where practice	il, search terms use	d)
	¥ .			
C. DOCUM	ENTS CONSIDERED TO BE RELEVANT			
Category *	Citation of document, with indication, where appropriate, of the	relevant passages		Relevant to claim No.
X	US 4 655 760 A (WISNESKI TONY J 7 April 1987 (1987-04-07) column 6, line 55 -column 7, li figure 2			34
A	WO 93 14928 A (RASMUSSEN O B ;J MARJORIE MEREDITH (GB)) 5 August 1993 (1993-08-05) claim 1	ONES HELEN		1,11,24, 32-34
A	WO 91 15365 A (MINNESOTA MINING 17 October 1991 (1991-10-17) figure 3	& MFG)		1,11,24, 32-34
A	US 4 443 511 A (WORDEN DEXTER   17 April 1984 (1984-04-17) figure 6A	ET AL)		1
		-/	j	
		,		
X Furth	er documents are listed in the continuation of box C.	X Patent family	members are listed i	in annex.
* Special cat	egories of cited documents:	To later document with	lahad attache later	
"A" documer conside	nt defining the general state of the art which is not ered to be of particular relevance	"T" later document publi or priority date and cited to understand	not in conflict with the the principle or the	the application but
"E" earlier d	ocument but published on or after the international	"X" document of particu	lar relevance: the cl	almed invention
"L" documer	nt which may throw doubts on priority claim(s) or s cited to establish the publication date of another	canylor de conside injulve an inventiv	red novel or cannot: a step when the doc	be considered to sument is taken alone
O docume	or other special reason (as specified) nt referring to an oral disclosure, use, exhibition or	"Y" document of particu cannot be consider	red to involve an inv	almed invention entive step when the re other such docu—
ouner m	seans It published prior to the international filing date but	ments, such combi	nation being obviou	s to a person skilled
latter tric	an the phorny date claimed	*&* document member of	of the same patent for	amily
∼ora ni Me 9	ctual completion of the international search	Date of mailing of the	he international sear	rch report
9	May 2000	18/05/20	000	
Name and m	ailing address of the ISA European Patent Office, P.B. 5818 Patentiaan 2	Authorized officer		
	NL - 2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,			
	Fax: (+31-70) 340-3016	Barathe,	, R	

Inte. onal Application No PCT/US 99/30729

DOCUMENTS CONSIDERED TO BE RELEVANT  ton of document, with indication, where appropriate, of the relevant passages  NO 97 02378 A (KIMBERLY CLARK CO) 23 January 1997 (1997-01-23) figure 1  US 5 336 545 A (MORMAN MICHAEL T) 25 August 1994 (1994-08-09) 25 tited in the application 26 the whole document 27 May 1996 (1996-05-07) 28 the whole document 28 5 536 555 A (ZELAZOSKI GREGORY A ET 28 L) 16 July 1996 (1996-07-16) 29 the whole document 29 0 419 742 A (EXXON CHEMICAL PATENTS 20 NC) 3 April 1991 (1991-04-03) 20 the whole document	1,11 1-34 1,11 1,11
NO 97 02378 A (KIMBERLY CLARK CO) 23 January 1997 (1997-01-23) figure 1  US 5 336 545 A (MORMAN MICHAEL T) 25 August 1994 (1994-08-09) 26 ited in the application 27 August 1994 (HAFFNER WILLIAM B ET AL) 28 May 1996 (1996-05-07) 29 He whole document  US 5 536 555 A (ZELAZOSKI GREGORY A ET AL) 29 LO 419 742 A (EXXON CHEMICAL PATENTS 20 NC) 3 April 1991 (1991-04-03)	1,11 1-34 1,11
## Page 1	1-34 1,11 1,11
August 1994 (1994-08-09) Eited in the application The whole document  IS 5 514 470 A (HAFFNER WILLIAM B ET AL) May 1996 (1996-05-07) The whole document  IS 5 536 555 A (ZELAZOSKI GREGORY A ET AL) TO July 1996 (1996-07-16) The whole document The Whole May 1991 (1991-04-03)	1,11
May 1996 (1996-05-07) The whole document  S 5 536 555 A (ZELAZOSKI GREGORY A ET IL) 16 July 1996 (1996-07-16) The whole document  P 0 419 742 A (EXXON CHEMICAL PATENTS NC) 3 April 1991 (1991-04-03)	1,11
L) 16 July 1996 (1996-07-16)  he whole document   P 0 419 742 A (EXXON CHEMICAL PATENTS  NC) 3 April 1991 (1991-04-03)	
NC) 3 April 1991 (1991-04-03)	1
<del></del>	
P 0 321 985 A (KIMBERLY CLARK CO) 8 June 1989 (1989-06-28) he whole document 	1-34
·	
	he whole document P 0 321 985 A (KIMBERLY CLARK CO) B June 1989 (1989-06-28)

information on patent family members

Inte onal Application No PCT/US 99/30729

Pa	tent document		Publication		Patent family	99/30/29 Publication
cited	in search report		date		member(s)	date
US	4655760	A	07-04-1987	CA	1282202 A	02-04-1991
WO	9314928	Α	05-08-1993	AT	170453 T	15-09-1998
				AU	3364893 A	01-09-1993
				AU	681059 B	14-08-1997
				AU	5467696 A	01-08-1996
				BG	98911 A	28-07-1995
				BR	9305790 A	18-02-1997
				CA	2126759 A	05-08-1993
				CN	1083772 A	16-03-1994
				CN	1192398 A	09-09-1998
				CN CZ	1192402 A 9401790 A	09-09-1998
				DE	69320789 D	14-06-1995
				DE	69320789 T	08-10-1998 20-05-1999
				EP	0624126 A	20-05-1999 17-11-1994
				ES.	2123636 T	16-01-1999
				FI	943501 A	25-07-1994
				НŪ	73831 A	30-09-1996
				IL	104487 A	16-10-1996
				ĴΡ	7505586 T	22-06-1995
				MX	9300462 A	01-07-1993
				NO	942738 A	28-09-1994
				NO	974559 A	28-09-1994
				NZ	246673 A	25-09-1996
				PL	171177 B	28-03-1997
				PL	172357 B	30-09-1997
				RO	114312 A	30-03-1999
				SG	50371 A	20-07-1998
				TR	28420 A	19-06-1996
				US	5626944 A	06-05-1997
				ZA Zw	9300555 A 1893 A	19-10-1993
					1093 A	21-09-1994 
WO	9115365	Α	17-10-1991	AT	152670 T	15-05-1997
				AU	637678 B	03-06-1993
				AU	7318491 A	30-10-1991
			•	CA	2076031 A	01-10-1991
				DE	69126021 D	12-06-1997
				DE Ep	69126021 T 0521875 A	09-10-1997 13-01-1993
				ES	2100946 T	01-07-1993
				JP	3007414 B	07-07-1997
				KR	9600740 B	12-01-1996
				MX	173715 B	23-03-1994
				US	5354597 A	11-10-1994
US	4443511	A	17-04-1984	AT	29745 T	15-10-1987
				AU	565226 B	10-09-1987
				AU	2192983 A	13-09-1984
				CA	1198045 A	17-12-1985
				DE	3373686 D	22-10-1987
				DK	529783 A	20-05-1984
				EP	0110626 A	13-06-1984
				ES	527376 D	16-11-1984
				ES	8501463 A	16-02-1985
				ES	533757 D	01-05-1985
				ES	8504555 A	16-07-1985
m PCT//SA/210 /	patent family annex) (.	hrby 1002)				

information on patent family members

Inte .onal Application No PCT/US 99/30729

Patent document cited in search repo	rt	Publication date		Patent family member(s)	Publication date
US 4443511	A	L L.	FI	834175 A,B,	20-05-1984
	• •		GB	2130525 A,B	06-06-1984
			GR	79074 A	02-10-1984
			ĬĔ	54745 B	17-01-1990
			ĪĹ	70250 A	31-01-1988
			ÎN	161392 A	28-11-1987
			JP	1719858 C	14-12-1992
			JP	4003741 B	24-01-1992
			JP	59187845 A	25-10-1984
			KR	8802642 B	08-12-1988
			NO	834241 A,B,	21-05-1984
			NZ	206320 A	08-10-1986
			PL	244643 A	22-10-1984
		<del></del>		247043 A	22-10-1904
WO 9702378	A	23-01-1997	US	5814390 A	29-09-1998
			AU	694372 B	16-07-1998
			AU	6289696 A	05-02-1997
			CA	2222443 A	23-01-1997
			CN	1193363 A	16-09-1998
		···	EP	0835339 A	15-04-1998
US 5336545	A	09-08-1994	US	5226992 A	13-07-1993
			US	5514470 A	07-05-1996
			AT	110801 T	15-09-1994
			AU	626599 B	06-08-1992
			AU	4418589 A	18-04-1990
			CA	1339061 A	29-07-1997
			DE	68917915 D	06-10-1994
			DE	68917915 T	22-12-1994
			EP	0400111 A	05-12-1990
			ES	2021173 A	16-10-1991
			JP	3501508 T	04-04-1991
			KR	127340 B	06-04-1998
			MX	172309 B	13-12-1993
		، ورد شرور بساخت کا ناد کا پندی پیرور باک کا	WO	9003464 A	05-04-1990
US 5514470	Α	07-05-1996	US	5336545 A	09-08-1994
		•	US	5226992 A	13-07-1993
			AU	688509 B	12-03-1998
			AU	2506495 A	01-02-1996
			CA	2138327 A	20-01-1996
			EP	0707106 A	17-04-1996
			ZA	9505714 A	21-02-1996
			AT	110801 T	15-09-1994
			AU	626599 B	06-08-1992
			AU	4418589 A	18-04-1990
			CA	1339061 A	29-07-1997
			DE	68917915 D	06-10-1994
			DE	68917915 T	22-12-1994
			EP	0400111 A	05-12-1990
			ES	2021173 A	16-10-1991
			JP	3501508 T	04-04-1991
			KR	127340 B	06-04-1998
			MX	172309 B	13-12-1993
			WO	9003464 A	05-04-1990
 US 5536555	A	16-07-1996	AU	1866495 A	10-07-1995

information on patent family members

Inter onal Application No PCT/US 99/30729

Patent document cited in search report		Publication date	Patent family member(s)		Publication date
US 5536555	A	·	FR GB TR WO ZA	2713982 A 2284786 A,B 28306 A 9517301 A 9410025 A	23-06-1995 21-06-1995 17-04-1996 29-06-1995 22-08-1995
EP 0419742	A	03-04-1991	US . JP	4880682 A 3128234 A	14-11-1989 31-05-1991
EP 0321985	A	28-06-1989	US AU CA JP MX ZA	4847134 A 2730288 A 1317699 A 2004365 A 166275 B 8809549 A	11-07-1989 22-06-1989 18-05-1993 09-01-1990 28-12-1992 29-11-1989